




ALTERNATIVE 1 : WITH SPLAYS
SCALE 1:200



ALTERNATIVE 2 : NO SPLAYS
SCALE 1:200



POSITION OF METER BOXES IN PAN HANDLES



NORMAL POSITION OF METER BOXES
(REFER TO DWG STD-WR-010)

NOTES AND SPECIFICATIONS

GENERAL

1. MINIMUM REQUIREMENTS ARE INDICATED ON THE DRAWING. THE CONSULTANT / DESIGNER IS RESPONSIBLE AND LIABLE FOR FURTHER DETAILS AND TO ENSURE EFFECTIVE OPERATION AND MAINTENANCE OF THE INSTALLATION.
2. THE SIGNATURE OR INITIALS ON THIS DRAWING OF COE OFFICIAL DOES NOT REMOVE ANY RESPONSIBILITY WHATSOEVER FROM THE CONSULTANT / DESIGNER.
3. THE CONSULTANT / DESIGNER REMAINS RESPONSIBLE TO ENSURE THAT ALL THE GUIDELINES, STANDARD DRAWINGS, STANDARDS AND SPECIFICATIONS OF THE WATER AND SANITATION DEPARTMENT HAVE BEEN MET AND ARE COMPLIED WITH IN THE DESIGN.
4. ALL MATERIAL AND WORKMANSHIP MUST COMPLY WITH THE REQUIREMENTS OF THE LATEST RELEVANT SANS STANDARD.
5. FINAL POSITION OF SERVICES TO BE DETERMINED ON SITE.
6. ALL DIMENSIONS TO BE CHECKED AND APPROVED ON SITE.
7. ALL DIMENSIONS ARE IN mm (UNLESS OTHERWISE SPECIFIED).
8. DO NOT SCALE FROM THESE DRAWINGS.
9. CLASS OF CONCRETE UNLESS OTHERWISE SPECIFIED ON DRAWING DETAILS:
REINFORCED CLASS 30/19
THRUST BLOCKS CLASS 20/19
BLINDING CLASS 15/19
FLOOR SCREED SAND : CEMENT = 3 : 1
10. PRE-CAST CONCRETE RINGS AND COVER SLABS TO COMPLY WITH SANS 1294.
11. JOINTS BETWEEN CONCRETE RINGS AND BETWEEN COVER SLABS AND BETWEEN RINGS AND FLOORS TO BE SEALED WITH BITUMEN SEALANT (APPROVED BY THE DESIGNER).
12. ALL JOINTS BETWEEN THE PIPE AND THE CHAMBER WALL AND BETWEEN BRICK WALL AND CONCRETE FLOOR TO BE SEALED TO PREVENT WATER LEAKING INTO THE CHAMBER. METHOD OF SEALING TO BE SUBMITTED TO THE DESIGNER FOR APPROVAL.
13. FLANGE DRILLING TO BE IN ACCORDANCE WITH SANS 1123. DESIGNER TO SPECIFY FLANGE TABLE.
14. ALL BOLTS, WASHERS AND NUTS TO BE HOT DIPPED GALVANISED IN ACCORDANCE WITH SANS 763.
15. ALL STEEL PIPE ITEMS TO BE GRIT BLASTED TO SA 3 OF ISO 8501-1 AND PAINTED WITH EPOXY COMPLYING WITH SANS 1217 WITH A MINIMUM DRY FILM THICKNESS OF 500 MICRON (LINING AND COATING). UNDERGROUND STEEL PIPE ITEMS TO BE WRAPPED WITH PETROLATUM TAPE (APPROVED BY DESIGNER) OVER THE EPOXY COATING.
16. CONCRETE SUPPORTS ARE REQUIRED UNDERNEATH VALVES AND PIPE WORK WHERE INDICATED BY THE DESIGNER.
17. DESIGNER TO SPECIFY STEP IRONS OR LADDER INSIDE CHAMBER. STEP IRONS TO BE SALBERG AND BUILT-IN.
18. THERE MUST BE NO CONTACT BETWEEN STEEL PIPE ITEMS AND CONCRETE OR BRICK REINFORCEMENT.

PARTICULAR

1. THE LETTER "W" IS TO BE FORMED IN THE CONCRETE KERB OF ALL NEW ROADS (REFER TO DWG. NO. STD-WR-003) TO INDICATE THE POSITION OF WATER RETICULATION PIPE LINES.
2. REFER TO SERVICES LAYOUT DRAWINGS FOR WATER RETICULATION PIPE POSITION IN THE ROAD RESERVE.



City of Ekurhuleni
WATER AND SANITATION DEPARTMENT

AMENDMENTS			
NR	DATE	APPROVED	DESCRIPTION

WATER AND SANITATION	
APPROVED ON BEHALF OF: OPERATIONS DIVISION	
NAME:.....	PROF REG No:.....
SIGNATURE:.....	DATE:.....
PROJECTS DIVISION	
NAME:.....	PROF REG No:.....
SIGNATURE:.....	DATE:.....
PLANNING DIVISION	
NAME:.....	PROF REG No:.....
SIGNATURE:.....	DATE:.....

CONSULTANT DETAILS TO BE PLACED HERE	DESIGNED	CONTRACT No.	PROJECT TITLE
	NAME:.....	PROJECT No.	STANDARD GUIDELINE DRAWINGS
	SIGNATURE:..... DATE:.....	SHEET No.	DRAWING TITLE
	DRAWN	PAPER SIZE	STANDARD DRAWING: WATER RETICULATION PLACING OF HYDRANTS, VALVES, HOUSE CONNECTIONS & MARKERS
	NAME:.....	A1	COE DRAWING NUMBER
	SIGNATURE:..... DATE:.....	SCALE	STD-WR-002
APPROVED	CONSULTANT DRAWING NUMBER		
NAME:..... PROF REG No:.....			
SIGNATURE:..... DATE:.....			

REVISION	REVISION
----------	----------